

PERRY JOHNSON LABORATORY ACCREDITATION, INC.

Certificate of Accreditation

Perry Johnson Laboratory Accreditation, Inc. has assessed the Laboratory of:

Doble Engineering Company 1520 South Hellman Avenue, Ontario, CA 91761

(Hereinafter called the Organization) and hereby declares that Organization is accredited in accordance with the recognized International Standard:

ISO/IEC 17025:2017

This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality management system (as outlined by the joint ISO-ILAC-IAF Communiqué dated April 2017):

Dimensional, Electrical, Time & Frequency Calibration (As detailed in the supplement)

Accreditation claims for such testing and/or calibration services shall only be made from addresses referenced within this certificate. This Accreditation is granted subject to the system rules governing the Accreditation referred to above, and the Organization hereby covenants with the Accreditation body's duty to observe and comply with the said rules.

For PJLA:

Jeacy Szusper

Tracy Szerszen President

Perry Johnson Laboratory Accreditation, Inc. (PJLA) 755 W. Big Beaver, Suite 1325 Troy, Michigan 48084

Initial Accreditation Date:	Issue Date:	Expiration Date:
September 30, 2017	September 13, 2019	October 31, 2021
Revised date:	Accreditation No.:	Certificate No.:
October 8, 2020	85299	L19-451-R1

The validity of this certificate is maintained through ongoing assessments based on a continuous accreditation cycle. The validity of this certificate should be confirmed through the PJLA website: <u>www.pjlabs.com</u>



Certificate of Accreditation: Supplement

Doble Engineering Company

1520 South Hellman Avenue, Ontario, CA 91761 Contact Name: Tim Nguyen Phone: 909-923-9390

Accreditation is granted to the facility to perform the following calibrations:

Dimensional

MEASURED INSTRUMENT, QUANTITY OR GAUGE	RANGE OR NOMINAL DEVICE SIZE AS APPROPRIATE	CALIBRATION AND MEASUREMENT CAPABILITY EXPRESSED AS AN UNCERTAINTY (±)	CALIBRATION EQUIPMENT AND REFERENCE STANDARDS USED
Equipment to Measure	0.001 in to 1 in	0.01 in/in + 0.07 in	Vanguard CT-7500
Distance -Linear Transducer ^F	1 in to 2 in	0.008 in/in + 0.06 in	Caliper Starrett 723
Talisuucei	2 in to 3 in	0.012 in/in + 0.21 in	

Electrical

MEASURED INSTRUMENT, QUANTITY OR GAUGE	RANGE OR NOMINAL DEVICE SIZE AS APPROPRIATE	CALIBRATION AND MEASUREMENT CAPABILITY EXPRESSED AS AN UNCERTAINTY (±)	CALIBRATION EQUIPMENT AND REFERENCE STANDARDS USED
Equipment to Measure DC Voltage ^F	100 mV to 1 V	$267 \mu V/V + 1.1 mV$	Fluke 8845A
	1 V to 10 V	331 μV/V + 1.4 mV	
	10 V to 100 V	15.5 mV/V + 272 mV	
	100 V to 200 V	19.7 mV/V + 346 mV	
	200 V to 250 V	15.5 mV/V + 272 mV	
	250 V to 300 V	35 mV/V + 623 mV	
	300 V to 1 kV	42 mV/V + 742 mV	
	1 kV to 10 kV	5.77 mV/V + 101.2 V	CPS HVP-500 High
	10 kV to 20 kV	5.77 mV/V + 101.2 V	Voltage Probe with Fluke
	20 kV to 30 kV	5.77 mV/V + 101.2 V	8845A
	30 kV to 40 kV	17.32 mV/V + 303.6 V	
	40 kV to 50 kV	23.09 mV/V + 404.8 V	
	50 kV to 60 kV	11.3 mV/V + 202.4 V	
	60 kV to 70 kV	11.5 mV/V + 202.4 V	
	70 kV to 75 kV	5.77 mV/V + 101.2V	k l
Equipment to Output	0.1 V to 1 V	267 μV/V + 1.1 mV	Fluke 8845A
DC Voltage ^F	1 V to 10 V	$331 \mu\text{V/V} + 1.4 \text{mV}$	
	10 V to 100 V	15.5 mV/V + 272 mV	
	100 V to 200 V	19.7 mV/V + 346 mV	
	200 V to 250 V	15.5 mV/V + 272 mV	
	250 V to 300 V	35 mV/V + 623 mV	
	300 V to 1 kV	42 mV/V + 742 mV	
	1 kV to 10 kV	5.77 mV/V + 101.2 V	CPS HVP-500 High
	10 kV to 20 kV	5.77 mV/V + 101.2 V	Voltage Probe with Fluke
	20 kV to 30 kV	5.77 mV/V + 101.2 V	8845A
	30 kV to 40 kV	17.32 mV/V + 303.6 V	1
	40 kV to 50 kV	23.09 mV/V + 404.8 V	1
Issue: 09/2019	This supplement is in conjun	tion with certificate #L19-45.	<i>1-R1 Page 2 of 5</i>



Certificate of Accreditation: Supplement

Doble Engineering Company

1520 South Hellman Avenue, Ontario, CA 91761 Contact Name: Tim Nguyen Phone: 909-923-9390

Accreditation is granted to the facility to perform the following calibrations:

MEASURED INSTRUMENT, QUANTITY OR GAUGE	RANGE OR NOMINAL DEVICE SIZE AS APPROPRIATE	CALIBRATION AND MEASUREMENT CAPABILITY EXPRESSED AS AN UNCERTAINTY (±)	CALIBRATION EQUIPMENT AND REFERENCE STANDARDS USED
Equipment to Output DC Voltage ^F	50 kV to 60 kV	11.5.3 mV/V + 202.4 V	CPS HVP-500 High Voltage Probe with Fluke 8845A
	60 kV to 70 kV	11.5 mV/V + 202.4 V	
	70 kV to 75 kV	5.77 mV/V + 101.2 V	
Equipment to Measure DC Current ^F	1 mA to 10 mA	4.1 μΑ/Α + 7.1 μΑ	Fluke 8845A with/Shunt
	10 mA to 1 A	602 μA/A + 10.5 mA	
	1 A to 5 A	3.5 mA/A + 61 mA	
	5A to 10A	6 mA/A + 105 mA	_
Equipment to Output	1 mA to 10 mA	4.1 μΑ/Α + 7.1 μΑ	_
DC Current ^F	10 mA to 1 A	602 μA/A + 10.5 mA	_
	1 A to 5 A	3.5 mA/A + 61 mA	_
	5 A to 10A	6 mA/A + 105 mA	_
Equipment to Measure	1 Ω to 10 Ω	$1.04 \text{ m}\Omega/\Omega + 8.05 \text{ m}\Omega$	Fluke 8845A
Resistance ^F	10 Ω to 100 Ω	$0.82 \text{ m}\Omega/\Omega + 6.3 \text{ m}\Omega$	
	100 Ω to 1 000 Ω	$1.06 \text{ m}\Omega/\Omega + 17.8 \text{ m}\Omega$	_
	1 000 Ω to 1 900 Ω	2.43 mΩ/Ω-+ 26.5 mΩ	
	1.9 k Ω to 200 k Ω	$0.2 \Omega/\Omega + 3.5 \Omega$	\supset
	200 k Ω to 1 M Ω	$0.51 \Omega/\Omega + 8.9 \Omega$	
Equipment to Output	0 A to 1 A	602 μA/A + 10.5 mA	Fluke 8845A with/Shunt
AC Current ^F	1 A to 5 A	5.8 mA/A + 101 mA	-
	5 A to 10 A	1.5 mA/A + 26 mA	
	10 A to 100 A	10 mA/A + 175 mA	_
	100 A to 400 A	10 mA/A + 175 mA	
	400 A to 600 A	10 mA/A + 175 mA	
Equipment to Measure AC (at the listed frequencies) ^F	Current		
40 Hz to 100 Hz	100 mA to 1A	602 μA/A + 10.5 mA	
	1 A to 5 A	5.8 mA/A + 101 mA	
	5 A to 10 A	1.5 mA/A + 26 mA	



Certificate of Accreditation: Supplement

Doble Engineering Company

1520 South Hellman Avenue, Ontario, CA 91761 Contact Name: Tim Nguyen Phone: 909-923-9390

Accreditation is granted to the facility to perform the following calibrations:

MEASURED INSTRUMENT, QUANTITY OR GAUGE	RANGE OR NOMINAL DEVICE SIZE AS APPROPRIATE	CALIBRATION AND MEASUREMENT CAPABILITY EXPRESSED AS AN UNCERTAINTY (±)	CALIBRATION EQUIPMENT AND REFERENCE STANDARDS USED
Equipment to Measure AC Voltage (at the listed frequencies) ^F			Fluke 8845A
40 Hz to 100 Hz	100 mV to 1 V	$42.4 \ \mu V/V + 214 \ \mu V$	
	1 V to 10 V	$242.7 \mu V/V + 4.2 mV$	
	10 V to 100 V	155.7 μV/V + 2.7 mV	
	100 V to 200 V	2.18 mV/V + 38.2 mV	
	200 V to 250 V	29.4 mV/V + 516.6 mV	
	250 V to 300 V	47.2 mV/V + 823.1 mV	
Equipment to Output AC Vo (at the listed frequencies) ^F	bltage		
40 Hz to 100 Hz	100 mV to 1V	42.4 μV/V + 214 uV	
	1 V to 10 V	$242.7 \mu V/V + 4.2 mV$	
	10 V to 100 V	155.7 μV/V + 2.7 mV	
	100 V to 200 V	2.18 mV/V + 38.2 mV	
	200 V to 250 V	29.4 mV/V + 516.6 mV	
	250 V to 300 V	47.2 mV/V + 823.1 mV	

Time & Frequency

MEASURED INSTRUMENT, QUANTITY OR GAUGE	RANGE OR NOMINAL DEVICE SIZE AS APPROPRIATE	CALIBRATION AND MEASUREMENT CAPABILITY EXPRESSED AS AN UNCERTAINTY (±)	CALIBRATION EQUIPMENT AND REFERENCE STANDARDS USED
Equipment to Output	1 Hz to 15 Hz	0.36 mHz/Hz + 6.34 mHz	Tektronix TDS2014B
Frequency at 3 Vrms ^F	15 Hz to 60 Hz	1.86 mHz/Hz + 32.6 mHz	
	60 Hz to 250 Hz	4.01 mHz/Hz + 70 mHz	k.
	250 Hz to 500 Hz	9.5 mHz/Hz + 166.5 mHz	

1. The CMC (Calibration and Measurement Capability) stated for calibrations included on this scope of accreditation represents the smallest measurement uncertainty attainable by the laboratory when performing a more or less routine calibration of a nearly ideal device under nearly ideal conditions. It is typically expressed at a confidence level of 95 % using a coverage factor k (usually equal to 2). The actual measurement uncertainty associated with a specific calibration performed by the laboratory will typically be larger than the CMC for the same calibration since capability and performance of the device being calibrated and the conditions related to the calibration may reasonably be expected to deviate from ideal to some degree.



Certificate of Accreditation: Supplement

Doble Engineering Company

1520 South Hellman Avenue, Ontario, CA 91761 Contact Name: Tim Nguyen Phone: 909-923-9390

Accreditation is granted to the facility to perform the following calibrations:

- 2. The laboratories range of calibration capability for all disciplines for which they are accredited is the interval from the smallest calibrated standard to the largest calibrated standard used in performing the calibration. The low end of this range must be an attainable value for which the laboratory has or has access to the standard referenced. Verification of an indicated value of zero in the absence of a standard is common practice in the procedure for many calibrations but by its definition it does not constitute calibration of zero capacity.
- 3. The presence of a superscript F means that the laboratory performs calibration of the indicated parameter at its fixed location. Example: Outside Micrometer^F would mean that the laboratory performs this calibration at its fixed location.

